

## Town of Canton

### Aquatic Center Buildings Scope of Work

#### 783863 Champion Credit Union Aquatics Center Buildings

The applicant will utilize contract labor, equipment, materials, to complete repairs to the building to restore this facility back its pre-disaster design, function, and capacity within the existing footprint. Building exterior sheathing, electrical and pump house repairs were completed under separate SOWs. Mitigation includes wet proofing the concessions, ticket booth, office, and 3 bathrooms through the use of alternative water-resistant materials.

#### **Concession Stand Building:**

- A. Caulk and Paint 992 SF exterior siding (materials supplied by the Town).
- B. Install 1,064 SF of medium density closed cell spray foam insulation, cementitious backer board, fiberglass mesh and white finish coat stucco on interior walls (includes 2 half walls)

#### **Locker Room Building:**

- C. Caulk and Paint 1232 SF exterior siding (materials supplied by the Town).

#### **Ticket Booth/Bathrooms/Office building:**

- D. Caulk and Paint 928 SF exterior siding (materials supplied by the Town).

#### **Ticket Booth:**

- E. Install 165 SF of medium density closed cell spray foam insulation, cementitious backer board, fiberglass mesh and white finish coat stucco on interior walls.

#### **Office:**

- F. Install 260 SF of medium density closed cell spray foam insulation, cementitious backer board, fiberglass mesh and white finish coat stucco on interior walls.

#### **Women's Bathroom:**

- G. Install 116 SF of medium density closed cell spray foam insulation, cementitious backer board, fiberglass mesh and white finish coat stucco on interior walls.

#### **Men's Bathroom:**

- G. Install 116 SF of medium density closed cell spray foam insulation, cementitious backer board, fiberglass mesh and white finish coat stucco on interior walls.

#### **Private Bathroom:**

- G. Install 104 SF of medium density closed cell spray foam insulation, cementitious backer board, fiberglass mesh and white finish coat stucco on interior walls.

#### **Deductive Alternate**

Install Sequentia 48-in x 96-in Embossed White Wall Panels (including bonding adhesive; vinyl moldings for seams, ends and corners and vinyl floor base molding) in lieu of fiberglass mesh and white finish coat stucco for all interior walls.